

PLANT SCHEDULE:

TREES - BASE BID

KEY	QTY	BOTANICAL NAME	COMMON NAME	CALIPER	HEIGHT	SPREAD	METHODS	REMARKS
LS	7	LIQUIDAMBAR STYRACIFLUA 'ROTUNDILOBA'	SEEDLESS SWEET GUM	2" - 2.5"			1	PLANT AS SHOWN
INS	5	ILEX X 'NELLIE R. STEVENS'	NELLIE STEVENS HOLLY		5' - 6'		2	PLANT 10' O.C.

TREES - BID OPTION

KEY	QTY	BOTANICAL NAME	COMMON NAME	CALIPER	HEIGHT	SPREAD	METHODS	REMARKS
LS	7	LIQUIDAMBAR STYRACIFLUA 'ROTUNDILOBA'	SEEDLESS SWEET GUM	2" - 2.5"			1	PLANT AS SHOWN
INS	33	ILEX X 'NELLIE R. STEVENS'	NELLIE STEVENS HOLLY		5' - 6'		2	PLANT 10' O.C.

GENERAL PLANTING NOTES:

- ALL PLANT MATERIAL SHALL MEET THE MINIMUM SPECIFICATIONS AND STANDARDS DESCRIBED IN THE "AMERICAN STANDARD FOR NURSERY STOCK, 2004" (ANSI Z60.1-2004), PUBLISHED BY THE AMERICAN NURSERY AND LANDSCAPE ASSOCIATION, 1000 VERMONT AVENUE, NW, SUITE 300, WASHINGTON D.C. 20005-4914.
- PLANTING SEASON RESTRICTIONS: ALL BALLED AND BURLAPPED PLANTS SHALL BE INSTALLED BETWEEN OCTOBER 15 AND MARCH 31 UNLESS OTHERWISE AUTHORIZED BY THE LANDSCAPE ARCHITECT. ALL CONTAINER GROWN PLANTS SHALL BE INSTALLED BETWEEN SEPTEMBER 15 AND MAY 15 UNLESS OTHERWISE AUTHORIZED BY THE LANDSCAPE ARCHITECT.
- FINISHED GRADES ON GRADING PLAN THAT OCCUR IN SHRUB BEDS SPECIFY TOP OF FINISHED MULCH GRADES. LANDSCAPE CONTRACTOR SHALL NOT EXCEED THESE GRADES WHEN BEDS ARE COMPLETE WITH MULCH INSTALLED. IF LANDSCAPE CONTRACTOR ENCOUNTERS EARTHWORK CONDITIONS THAT WILL RESULT IN FINISHED MULCH TREATMENT EXCEEDING GRADES SPECIFIED ON GRADING PLAN, THEN THE LANDSCAPE CONTRACTOR SHALL NOTIFY THE GENERAL CONTRACTOR OF SUCH CONDITIONS. UNDER NO CIRCUMSTANCES SHALL FINISHED BED GRADES INCLUDING TOP OF MULCH EXCEED THE GRADE ELEVATIONS AS PROVIDED FOR BY THE GRADING PLAN.
- TOP OF MULCH SHALL FINISH 1" BELOW ADJACENT CONCRETE.
- VERIFICATION OF TOTAL QUANTITIES AS SHOWN IN THE "PLANT SCHEDULE" SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. THE PLANTING PLAN SHALL GOVERN.
- NEW PLANTING SHALL BE LOCATED AS SHOWN ON PLANS. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING THE LOCATION OF ALL SITE ELEMENTS AND UTILITIES. IF DISCREPANCIES OCCUR, OR IF OBSTRUCTIONS BELOW GROUND OR OVERHEAD ARE ENCOUNTERED, THE CONTRACTOR SHALL NOTIFY THE LANDSCAPE ARCHITECT. NECESSARY ADJUSTMENTS SHALL BE MADE ONLY UPON APPROVAL OF THE LANDSCAPE ARCHITECT.
- ALL PLANTING PITS AND BEDS SHALL BE BACKFILLED WITH PREPARED SOIL MIXTURE TO THE REQUIRED DEPTH AS SPECIFIED IN THE METHODS BELOW. WHERE A SHRUB OR GROUND COVER BED OCCURS AND FOR ALL HEDGES, THE ENTIRE BED SHALL BE PREPARED CONTINUOUSLY WITH SOIL MIXTURE TO THE REQUIRED DEPTH AS SPECIFIED.
- ALL SHRUBS AND GROUND COVERS ARE TO BE MAINTAINED SO AS TO GROW TOGETHER AND FORM A MASS. PRUNING (TRIMMING, SHEARING, ETC.) SHALL BE LIMITED TO THINNING AS NECESSARY. THE NATURAL GROWTH AND FORM OF THE PLANT SHALL BE MAINTAINED WITHOUT DAMAGE TO PRIMARY AND SECONDARY LEADERS.
- ALL TREES SHALL BE SINGLE LEADER SPECIMENS UNLESS OTHERWISE NOTED.
- ALL PLANT MATERIAL SHALL BE TRUE TO NAME AND SIZE, AND IN A HEALTHY AND THRIVING CONDITION AT INSTALLATION AND AT TIME OF INSPECTION. THE OWNER AND LANDSCAPE ARCHITECT RESERVE THE RIGHT TO REJECT ALL DISEASED, DYING OR STRESSED PLANT MATERIAL AT ANY TIME DURING THE PROJECT.
- ALL NEW TREES SHALL BE MULCHED WITHIN A MINIMUM TWO AND ONE HALF (2 1/2) FOOT RADIUS PLANTING AREA. ALL SHRUBS SHALL BE MULCHED WITHIN A ONE HALF-FOOT AREA OF THE PLANT.

**MALLER
TODD &
SADLER**
ARCHITECTS

DATE ISSUED: APRIL 04, 2012
DRAWN BY: DJC
SCALE: 1" = 60'-0"
SKETCH NUMBER: SKC-02

PLANT SCHEDULE AND METHODS

SUFFOLK POLICE RESPONSE FACILITY
3903 BRIDGE RD. SUFFOLK, VA

THIS SKETCH MODIFIES SHEET L-200

