

| Location UPC 100937 | Roadway Cut | Root Mat In Cut Sections | Root Mat in Fill Sections | Cut-Ditches | Fill-Ditches | Unsuitable Material | | Roadway Fill | Entrances | | Total Regular Excavation | Total Fill | Demolition of Pavement | Minor Structure Excavation | Stormwater Management Basins | | Borrow |
|------------------------|----------------|--------------------------------|---------------------------------|-------------|--------------|---------------------|-------------------|-----------------|-----------|------|--------------------------------|------------|---------------------------|-------------------------------|------------------------------------|------|--------|
| | | | | | | Below Subgrade | Above Subgrade | | Cut | Fill | | | | | Cut | Fill | |
| | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY |
| Route 58 | 8609 | 1888 | 42891 | | | | 6999 | 100943 | | | 89500 | 143834 | | | 38000 | | |
| Side Roads | 3500 | | | | | | | 1450 | | | 3500 | 1450 | | | | | |
| FORMULAS | C | D | E | F | G | H | I | J | K | L | M | N | O | P | Q | R | S |
| TOTALS | 12109 | 1888 | 42891 | 0 | 0 | 0 | 6999 | 102393 | 0 | 0 | 93000 | 145284 | 0 | 0 | 38000 | 0 | 120205 |
| | | | | | | | | | | | | | | | | | |
| Location UPC 104359 | Roadway Cut | Root Mat In Cut Sections | Root Mat in Fill Sections | Cut-Ditches | Fill-Ditches | Unsuitable Material | | Roadway Fill | Entrances | | Total Regular Excavation | Total Fill | Demolition of Pavement | Minor Structure Excavation | Stormwater Management Basins | | Borrow |
| | | | | | | Below Subgrade | Above Subgrade | | Cut | Fill | | | | | Cut | Fill | |
| | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY | CY |
| Route 58 | 653 | 169 | 2597 | | | | 11484 | 7935 | | | 14250 | 10532 | | | 11000 | | |
| Manning Bridge Road | 350 | 50 | 400 | | | | 300 | 768 | | | 750 | 1168 | | | | | |
| FORMULAS | C | D | E | F | G | H | I | J | K | L | M | N | O | P | Q | R | S |
| TOTALS | 1003 | 219 | 2997 | 0 | 0 | 0 | 11784 | 8703 | 0 | 0 | 15000 | 11700 | 0 | 0 | 11000 | 0 | 13000 |

| ROADWAY | TOTALS | 2" Asphalt Conc. Ty. SM-12.5E @ 220 lbs/sy | 6" Asphalt Concrete Ty. IM-19.0D @ 660 lbs/sy | 7" Asphalt Concrete Base Course Ty. BM-25.0A | 8" Aggr. Base Matl. Ty. 1 No. 21B | Geotextile (Subgrade Stab.) | Variable Depth Asphalt Concrete Ty. IM-19.0D (Buildup) | Variable Depth Asphalt Concrete Base Course Ty. BM-25.0A (Buildup) | 6" Aggr. Base Matl. Ty. 1 No. 21B | 4" Concrete Sidewalk |
|----------------------------------|--------|---|--|---|-----------------------------------|-----------------------------|---|---|-----------------------------------|----------------------|
| | SY | TON | TON | TON | TON | SY | TON | TON | TON | SY |
| Route 58 Full Depth | 98,266 | 10,810 | 32,428 | 37,833 | 43,631 | 98,266 | | | | |
| Phase 1 Temp Full Depth | 11,873 | 1,307 | 3,919 | 4,572 | 5,272 | 11,873 | | | | |
| Route 58 Build Up | 24,802 | 2,729 | | | | | 4,093 | 14,457 | | |
| Route 58 Mill and Overlay | 14,190 | 1,561 | | | | | | | | |
| Raleigh Drive Overlay | 325 | 36 | | | | | | | | |
| Beachwood Drive Overlay | 342 | 38 | | | | | | | | |
| Faifield Ave Overlay | 310 | 35 | | | | | | | | |
| Robin Ave Overlay | 526 | 58 | | | | | | | | |
| Forest Glenn Drive Overlay | 1,201 | 133 | | | | | | | | |
| Forest Glenn Drive Full Depth | 967 | 107 | 320 | 373 | 430 | 967 | | | | |
| Kenyon Road Overlay | 3,641 | 401 | | | | | | | | |
| Kenyon Road Full Depth | 2,198 | 242 | 726 | 847 | 976 | 2,198 | | | | |
| English Oak Drive Overlay | 330 | 37 | | | | | | | | |
| English Oak Drive Full Depth | 179 | 20 | 60 | 69 | 80 | 179 | | | | |
| Cameron Crossing Overlay | 371 | 41 | | | | | | | | |
| Cove Point Drive Overlay | 830 | 92 | | | | | | | | |
| Faulk Rd Overlay | 447 | 50 | | | | | | | | |
| Lakewood Drive Overlay | 567 | 63 | | | | | | | | |
| Barrett Drive Overlay | 169 | 19 | | | | | | | | |
| Barrett Drive Full Depth | 467 | 52 | 155 | 180 | 208 | 467 | | | | |
| Grove Ave Overlay | 677 | 75 | | | | | | | | |
| Manning Road Overlay | 839 | 93 | | | | | | | | |
| Manning Road Full Depth | 1,166 | 129 | 385 | 449 | 518 | 1,166 | | | | |
| Northbrook Road Overlay | 208 | 23 | | | | | | | | |
| Northbrook Road Full Depth | 1,469 | 162 | 485 | 566 | 653 | 1,469 | | | | |
| Centerpont Drive West Full Depth | 1,448 | 160 | 478 | 558 | 644 | 1,448 | | | | |
| Centerpont Drive East Full Depth | 610 | 68 | 202 | 235 | 271 | 610 | | | | |
| Staley Drive Full Depth | 786 | 87 | 260 | 303 | 350 | 786 | | | | |
| Concrete Sidewalk | 0 | 0 | | | | | | | | 6,800 |
| Asphalt Path | 14,151 | 1,557 | | | | | | | 4,713 | |
| TOTAL | | 20,185 | 39,418 | 45,985 | 53,033 | 119,430 | 4,093 | 14,457 | 4,713 | 6,800 |

| ROADWAY | TOTALS | 2" Asphalt Conc. Ty. SM-12.5E @ 220 lbs/sy | 6" Asphalt Concrete Ty. IM-19.0D @ 660 lbs/sy | 7" Asphalt Concrete Base Course Ty. BM-25.0A | 12" Asphalt Concrete Base Course Ty. BM-25.0A | 6" Aggr. Base Matl. Ty. 1 No. 21B | 8" Aggr. Base Matl. Ty. 1 No. 21B | Geotextile (Subgrade Stab.) |
|-------------------------|--------|---|--|---|--|-----------------------------------|-----------------------------------|-----------------------------|
| | SY | TON | TON | TON | | TON | TON | SY |
| BUILD UP OF EXIST. PVMT | 7,015 | 772 | 2,316 | | 4,631 | | | |
| MILL & OVERLAY | 3,192 | 352 | | | | | | |
| FULL DEPTH | 13,924 | 1,532 | 4,595 | 5,361 | | | 6,057 | 13,924 |
| SHARED USE PATH | 1,641 | 181 | | | | 547 | | |
| CONCRETE SIDEWALK | 747 | | | | | | | |
| TOTAL | | 2,837 | 6,911 | 5,361 | 4,631 | 547 | 6,057 | 13,924 |