

BID FORM

TO: Purchasing Division
 442 W. Washington Street
 Room 1086
 Suffolk, VA 23434-5237

BID: Lake Cohoon Bridge Rehabilitation

IFB: 21037-JS

DUE: November 10, 2020

TIME: 3:00 PM, Local

_____ (Company) quotes firm price(s) below, to furnish all labor, materials, equipment, transportation, licenses, permits, and fees required to complete the Lake Cohoon Road Over CSX Railroad Structure #8060 Bridge Rehabilitation project to the limits shown on the drawings in accordance with all specifications, terms, conditions, and drawings herein.

It is the intent of the City to award the bid in total. Should total costs exceed that budgeted for the projects, the City reserves the right to negotiate price with the lowest responsive and responsible bidder.

VDOT Item Code	Description	Qty.	Unit	Unit Price	TOTAL
ROAD CONSTRUCTION					
00110	CLEARING AND GRUBBING	1	LS		
10628	FLEXIBLE PAVE. PLANING 0"-2"	600	SY		
10636	ASPHALT CONC. TY. SM-9.5D	66	TON		
13283	GUARDRAIL GR-MGS1	1,956	LF		
13286	GUARDRAIL TERMINAL GR-MGS2	4	EA		
13394	FIXED OBJECT ATTACH. GR-FOA-5	4	EA		
24600	REMOVE EXIST. GUARDRAIL	2,276	LF		

10128	AGGR. BASE MATL. TY. 1 NO 21 B	25	TON		
MAINTENANCE OF TRAFFIC					
24152	TYPE 3 BARRICADE 8"	8	EA		
24160	CONSTRUCTION SIGNS	441	SF		
EROSION AND SEDIMENT CONTROL					
27505	TEMP. SILT FENCE	2,186	LF		
27430	SILTATION CONTROL EXCAVATION	372	CY		
SIGNING AND MARKING					
54032	TYPE B CLASS I PVMT LINE MRKG 4"	1,426	LF		
BRIDGE CONSTRUCTION					
68192	REPLACE BEARING	60	EA		
68201	MODIFY STEEL BEAM/GIRDER END	10	EA		
68590	JACKING AND BLOCKING	60	EA		
68043	CONCRETE LOW SHRINKAGE CLASS A4 MOD.	304.7	CY		
68090	BRIDGE DECK GROOVING	1,272	SY		
68085	COVER DEPTH SURVEY	1,272	SY		
62034	CONCRETE PARAPET AND CPSR 2 RAIL	804	LF		
68091	CORROSION RESISTANT REINFORCING STEEL, CLASS I	79,659	LB		
67087	PEDESTRIAN FENCE 8'	284	LF		
NS	STUD SHEAR CONNECTORS	465	EA		
69500	CONCRETE SUBSTRUCTURE SURFACE REPAIR	74	SY		

68172	CRACK REPAIR TYPE B	210	LF		
69011	STRUCTURE EXCAVATION	8	CY		
69740	CONCRETE SLAB SLOPE PROTECTION 4"	434	SY		
66123	DRY RIPRAP CL. A1 20"	319	SY		
68900	REMOVE PORTION OF EXISTING STRUCTURE (8060)	1	LS		
68472	RECOAT EXISTING STRUCTURE (8060)	1	LS		
68474	ENVIRONMENTAL PROTECTION AND HEALTH AND SAFETY	1	LS		
68490	DISPOSAL OF MATERIAL (8060, TYPE B)	1	LS		
ADDITIONAL PROJECT ITEMS					
00101	CONSTRUCTION SURVEYING (CONSTR.)	1	LS		
00100	MOBILIZATION	1	LS		
TOTAL BID AMOUNT					

Determination of low bidder shall be based on the TOTAL BID AMOUNT